



ADDENDUM No. 1 – (March 12, 2020)

ADDENDUM TO: Parking Lot Drainage Project, RJS

BID NUMBER: Bid #19-07

BID DUE DATE: Thursday, March 19, 2020 not later than 9:00am

TO BIDDER: This addendum is an integral part of the Bid file under consideration by you as a bidder in connection with the subject matter identified above. For the purpose of clarification, the following additions, changes, modifications and replacements noted below have been made to the Bid and have been made to the Bid file which bears the above title.

Bids submitted shall conform to these additions and modifications noted herein and including all issued addendums.

Clarifications per Pre-Bid Conference and the timeframe for the project, the following is the revision to the overall work scope:

1. Work area to have grass killer applied by TSA prior to any work start date.
2. At the initiation of work the contractor shall mix the grass matter into the top 12 inches of soil material to create a well-mixed top layer.
3. Install trench drain system per plan
4. Grade parking area per plan ensuring that 4 inches of sandy topsoil material is placed over the trench drain gravel layer.
5. Compact driving and parking areas to 90 to 95% compaction but leave areas over trench drain lightly compacted as to not impeded exfiltration.
6. Sod disturbed areas with Bahia sod or Hydroseed.
7. Water sod for 30 days (This will be done by TSA)

*ADDENDUM #1
Bid 19-07*

Note: To qualify your proposal, of which this addendum becomes a part, this form must be completed and returned to this office with the proposal.

Date: _____

Authorized Signature of Company Rep.

Printed Name of Company Rep.

Company: _____

Address: _____

Telephone: _____

Contact's Email: _____

END OF ADDENDUM #1